



GENERAL NOTES AND SPECIFICATIONS

- ALL CONSTRUCTION SHALL COMPLY WITH THE FRESNO MUNICIPAL CODE.
- GROUT ALL CELLS CONTAINING REINFORCING STEEL (SEE NOTE 9).
- ALL MASONRY UNITS SHALL COMPLY WITH THE LATEST ADOPTED CBC, CALIFORNIA BUILDING CODE.
- ALL MASONRY WALLS SHALL BE INSPECTED BY AN AGENCY APPROVED BY THE CITY OF FRESNO.
- DEPTH OF FOOTINGS ARE INTO NATURAL UNDISTURBED SOIL OR TESTED AND APPROVED COMPACTED FILL.
- ALL MASONRY UNITS SHALL BE MINIMUM , $f'_m = 1500$ PSI.
- REINFORCING BARS SHALL BE DEFORMED BARS MINIMUM GRADE 40.
- FOOTING CONCRETE SHALL BE A MINIMUM 2000 PSI AT 28 DAYS.
- ALL CELLS SHALL BE GROUTED SOLID IN CONDITIONS SUCH AS IN FRONTAGE ROAD ISLANDS OR AGAINST UNOCCUPIED AREAS SUCH AS RAILROAD RIGHTS OF WAY OR OTHER AREAS AS REQUIRED BY THE CITY ENGINEER.
- MORTAR SHALL BE TYPE -S (MINIMUM 1800 PSI AT 28 DAYS) ONE(1) PART CEMENT , TYPE - 1 ONE-HALF (1/2) PART LIME PUTTY OR HYDRATED LIME FOUR AND ONE-HALF (4 1/2) PARTS SAND (MAXIMUM).
- GROUT SHALL BE A MINIMUM 2000 PSI AT 28 DAYS ONE (1) PART CEMENT THREE (3) PARTS SAND TWO (2) PARTS PEA GRAVEL.