

NOTES:

- 1. REDWOOD BLOCKS SHALL BE CONSTRUCTION GRADE.
- 2. REDWOOD BLOCKS SHALL BE VEED TO FIT CONTOUR OF PIPE.
- 3. WHEN JACKING, CASING GRADE SHALL BE SET SO CENTER LINE OF CASING SHALL COINCIDE WITH CENTER LINE OF SEWER PIPE.
- 4. REDWOOD BLOCKS SHALL BE STRAPPED TO THE PIPE WITH STEEL STRAPPING OR APPROVED WIRE BANDS.
- 5. PLUG ENDS OF CASING WITH 12 INCHES MINIMUM OF CONCRETE.
- 6. CONCRETE SHALL BE CLASS "B" P.C.C..

REF. & REV. AUG. 2002 CITY OF FRESNO S-7