

NOTES:

- 1. ALL COPPER TUBING CONNECTIONS SHALL BE MADE WITH SILVER SOLDER.
- 2. PVC SCHEDULE 40 PIPE MAY BE SUBSTITUTED FOR COPPER PIPE.
- METAL HOUSING SHALL BE PRIMED AND PAINTED WITH A LIGHT GREEN, TAN OR GRAY EXTERIOR ENAMEL FINISH.
- 4. VALVE ASSEMBLY AND METAL HOUSING SHALL BE LOCATED IN MEDIAN ISLANDS, LANDSCAPE AREAS OR OUTSIDE OF SIDEWALK AREA WHERE POSSIBLE.

PROVIDE 4' MIN. SIDEWALK CLEARANCE ADJACENT TO AIR-VAC DEVICE FOR ADA ACCESSIBILTY REQUIREMENTS.

AUTOMATIC AIR RELEASE AND VACUUM VALVE

REF. & REV. AUG. 2002